

# MONTEREY COUNTY

## HOUSING AND COMMUNITY DEVELOPMENT

Erik V. Lunquist, AICP, Director



HOUSING, PLANNING, BUILDING, ENGINEERING, ENVIRONMENTAL SERVICES

1441 Schilling Place, South 2nd Floor  
Salinas, California 93901-4527

(831)755-5025  
www.co.monterey.ca.us  
**FORM UF**

### **PLEASE READ THIS DOCUMENT CAREFULLY**

The following conditions shall be considered as a part of Encroachment Permit No. \_\_\_\_\_.

All permit work shall conform to the current Standard Details and Specifications of the County of Monterey Department of Public Works and the State of California Standard Specifications.

A copy of this permit must be kept on the work site at all times and shall be exhibited upon demand by representatives of Public Works, the Fire Department, Police Department, and the Highway Patrol.

The Permittee shall give not less than forty-eight (48) hours notice of intent to work, exclusive of Saturdays, Sundays and Holidays.

### **NOTE: NO PERMIT SHALL BE CONSTRUED AS AUTHORITY TO CLOSE A ROAD**

Surplus materials shall be removed and disposed of and the work site left in a neat and workmanlike manner.

All Encroachment work must be adequately posted, signed, barricaded and lighted by the permittee.

Traffic signs and contractor warning devices shall be in accordance with the "Manual of Warning Signs, Lights and Devices for Use in Performance of Work upon Highways" issued by the State of California, Business and Transportation Agency, Department of Public Works.

Gradient area in back of curb to back of sidewalk shall be graded at plus two percent (+2%) from top of curb.

Permittee shall remove, replace, grade and compact minimum six inches (6") of Class 2 Aggregate Base and three inches (3") minimum of Type B Asphalt Concrete, one foot (1') minimum from edge of pavement to the new work.

Existing drainage shall be undisturbed or improved. Portland Cement Concrete for concrete curb, gutter, sidewalk and drive approaches, including repair work, shall consist of five (5) sacks Type 2 Class B Portland Cement Concrete, unless otherwise specified.

Construct a \_\_\_\_\_ foot Portland Cement Concrete approach to meet sidewalk grade.

A minimum of two inches (2") of compacted sand shall be placed under all new concrete work with a 4" P.C.C. (min) for sidewalks and curb return.

Existing curb shall be saw cut according to the requirements of the Standard Specifications.