Intersection						Existing Conditions	Background Conditions	Background + Project Conditions	Background + Alternative Project Site Plan Conditions	Cumulative + Project Conditions
	N-S Street	E-W Street	Existing Lane Configuration	Existing Intersection Control	LOS Standard					
1	Josselyn Canyon Road	Highway 68	NB 1-L, 1-R EB 1-T, 1-R WB 1-L, 1-T	Signal	C/D (Caltrans)	RI #1 1. Modify signal timing to provide additional green time to the Hwy 68 EBT movement	RI #12 1. Add 2nd Hwy 68 EBT 2. Add 2nd Hwy 68 WBT	Same As Background	Same As Background	Same As Background
2	Olmsted Road	Highway 68	NB 1-L/T/R SB 1-L/T, 1-R EB 1-L, 1-T, 1-R WB 1-L, 1-T, 1-R	Signal	C/D (Caltrans)	RI #2 1. Add 2nd Hwy 68 EBT 2. Add 2nd Hwy 68 WBT	Same As Existing	Same As Existing	Same As Existing	RI #16 1. Existing Improvements AND 2. Widen and restripe NB Olmsted to 1-L/T, 1-R 3. Convert NBR to RTO 4. Widen and restripe SB Olmsted to 2-L, 1-T, 1-R
3	Highway 218	Highway 68	NB 1-L, 1-T/R SB 2-L, 1-T, 1-R EB 1-L, 1-T, 1-T/R WB 1-L, 2-T, 1-R	Signal	C/D (Caltrans)	None Recommended	None Recommended	None Recommended	None Recommended	RI #17 1. Widen and restripe NB Monterra to 1-L, 1-T, 1-R 2. Widen and restripe EB Hwy 68 to 2-L, 1-T, 1-T/R 3. Convert Hwy 218 SBR to RTO
4	Ragsdale Drive	Highway 68	SB 2-R EB 1-L, 2-T WB 1-T, 1-T/R	Half Signal	C/D (Caltrans)	None Recommended	None Recommended	None Recommended	None Recommended	RI #18 1. Add 2nd Hwy 68 EBL
5	York Road	Highway 68	SB 1-L, 1-R EB 1-L, 1-T WB 1-T, 1-R	Signal	C/D (Caltrans)	RI #3 1. Add 2nd Hwy 68 WBT	Same As Existing	Same As Existing	Same As Existing	RI #19 1. Existing Improvements AND 2. Add 2nd Hwy 68 EBT 3. Add 2nd Hwy 68 EBL
6	Pasadera Drive-Boots Road	Highway 68	NB 1-L, 1-T/R SB 1-L/T, 1-R EB 1-L, 1-T, 1-R WB 1-L, 1-T, 1-R	Signal	C/D (Caltrans)	RI #4 1. Add 2nd Hwy 68 WBT	Same As Existing	Same As Existing	Same As Existing	RI #20 1. Existing Improvements AND 2. Add 2nd Hwy 68 EBT
7	Laureles Grade Road	Highway 68	NB 1-L, 1-R EB 1-T, 1-R WB 1-L, 1-T	Signal	C/D (Caltrans)	RI #5 1. Add 2nd Hwy 68 EBT 2. Add 2nd Hwy 68 WBT	Same As Existing	Same As Existing	Same As Existing	RI #21 1. Existing Improvements AND 2. Convert Laureles Grade NBR to RTO

Notes:

1. L, T, R = Left, Through, Right
2. NB, SB, EB, WB = Northbound, Southbound, Eastbound, Westbound
3. RTO = Right-turn overlap phasing
4. RI = Recommended Improvement

Intersection						Existing Conditions	Background Conditions	Background + Project Conditions	Background + Alternative Project Site Plan Conditions	Cumulative + Project Conditions
	N-S Street	E-W Street	Existing Lane Configuration	Existing Intersection Control	LOS Standard					
8	Corral de Tierra Road	Highway 68	NB 1-L, 1-R EB 1-T, 1-R WB 1-L, 1-T	Signal	C/D (Caltrans)	RI #6 1. Add 2nd Hwy 68 EBT 2. Add 2nd Hwy 68 WBT	Same As Existing	Same As Existing	Same As Existing	RI #22 1. Existing Improvements AND 2. Convert Corral de Tierra NBR to RTO
9	San Benancio Road	Highway 68	NB 1-L/T, 1-R SB 1-L/T, 1-R EB 1-L, 1-T, 1-R WB 1-L, 1-T/R	Signal	C/D (Caltrans)	RI #7 1. Add 2nd Hwy 68 EBT 2. Add 2nd Hwy 68 WBT	Same As Existing	Same As Existing	Same As Existing	Same As Existing
10	Paseo de Vaqueros	San Benancio Road	NB 1-L/T SB 1-T/R EB 1-L/R	Stop Sign (EB)	C (Mon. County)	None Recommended	None Recommended	None Recommended	None Recommended	None Recommended
11	Torero Drive	Highway 68	SB 1-L, 1-R EB 1-L, 1-T WB 1-T, 1-R	Stop Sign (SB)	C/D (Caltrans)	RI #8 1. Signalize 2. Add 2nd Hwy 68 WBT (This mitigation may not be applicable if four-lane section is extended)	RI #13 1. Existing Improvements AND 2. Add 2nd Hwy 68 EBT (This mitigation may not be applicable if four-lane section is extended)	Same As Background	Same As Background	Same As Background
12	Portola Drive	Highway 68 EB Ramps	NB 1-L, 1-T/R SB 1-L, 1-T/R EB 1-L/T/R WB 1-L/T/R	All-Way Stop	C/D (Caltrans)	None Recommended	None Recommended	None Recommended	None Recommended	None Recommended
13	Portola Drive	Highway 68 WB Ramps	NB 1-L, 1-T/R SB 1-L, 1-T/R EB 1-L/T/R WB 1-L/T/R	All-Way Stop	C/D (Caltrans)	None Recommended	None Recommended	None Recommended	None Recommended	RI #23 1. Signalize
14	Highway 68 EB Ramps	River Road	NB 1-L/T, 1-R EB 1-L, 1-T WB 1-T, 1-R	Signal	C/D (Caltrans)	None Recommended	None Recommended	None Recommended	None Recommended	RI #24 1. Add 2nd River Rd. EBL 2. And 2nd NB receiving lane on Hwy 68 EB On-ramp

Notes:

1. L, T, R = Left, Through, Right
2. NB, SB, EB, WB = Northbound, Southbound, Eastbound, Westbound
3. RTO = Right-turn overlap phasing
4. RI = Recommended Improvement

Intersection						Existing Conditions	Background Conditions	Background + Project Conditions	Background + Alternative Project Site Plan Conditions	Cumulative + Project Conditions
	N-S Street	E-W Street	Existing Lane Configuration	Existing Intersection Control	LOS Standard					
15	Highway 68 WB Ramps	Reservation Road	SB 1-L/T, 1-R EB 1-T/R WB 1-L, 1-T	Signal	C/D (Caltrans)	None Recommended	None Recommended	None Recommended	None Recommended	RI #25 1. Widen and restripe EB Reservation to 1-T, 1-R
16	Highway 68 WB Ramps	Spreckels Boulevard	SB 1-L/T/R EB 1-T/R WB 1-L/T	Stop Sign (SB)	C/D (Caltrans)	None Recommended	None Recommended	None Recommended	None Recommended	RI #26 1. Signalize 2. Add 2nd WB Spreckels LT (This will require a 2nd receiving lane on the WB Hwy 68 On-Ramp)
17	Highway 68 EB Offramp	Spreckels Boulevard	NB 1-L, 1-R EB 1-T WB 1-T	Stop Sign (NB)	C/D (Caltrans)	None Recommended	None Recommended	None Recommended	None Recommended	RI #27 1. Add 2nd Spreckels WBT 2. Restripe NB Hwy 68 Off-ramp LT to shared L/R 3. Add 2nd EB Spreckels receiving lane
18	Highway 68 EB Onramp	Spreckels Boulevard	SB 1-L, 1-R EB 1-L, 1-T WB 1-T, 1-R	Stop Sign (SB)	C/D (Caltrans)	None Recommended	None Recommended	None Recommended	None Recommended	RI #28 1. Add 2nd Spreckels EBT 2. Add 2nd Spreckels WBT
19	Highway 68	Blanco Road	NB 1-L, 2-T, 1-R SB 1-L, 2-T, 1-R EB 2-L, 2-T, 1-R WB 2-L, 1-T, 1-T/R	Signal	C/D (Caltrans)	RI #9 1. Add 2nd NB Hwy 68 LT 2. Convert NB Hwy 68 RT to free RT 3. Add 3rd WB Blanco LT 4. Convert WB Blanco T/R to through 5. Add WB Blanco RT 6. Adjust signal timing and convert SBR, EBR & WBR to RTO (See note 5)	Same As Existing Results in LOS D - PM Peak Hour	Same As Existing Results in LOS D - PM Peak Hour	Same As Existing Results in LOS D - PM Peak Hour	Same As Existing Results in LOS D - PM Peak Hour
20	Davis Road	Reservation Road	NB 1-L/T/R SB 1-L/T, 1-R EB 1-L, 1-T/R WB 1-L, 1-T/R	Stop Sign (NB & SB)	C (Mon. County)	RI #10 1. Signalize	RI #14 1. Existing Improvements AND 2. Add 2nd EB Reservation Rd. LT 3. Add EB Reservation Rd. through 4. Add WB Reservation Rd. through 5. Convert SBR to RTO	Same As Background	Same As Background	Same As Background
21	Davis Road	Blanco Road	NB 1-L, 1-T, 1-T/R SB 1-L, 1-T, 1-R EB 2-L, 1-T, 1-T/R WB 1-L, 2-T, 1-R	Signal	C (Mon. County)	RI #11 1. Convert NB Davis T/R to through 2. Add NB Davis RT 3. Add 2nd SB Davis LT 4. Add 2nd SB Davis RT 5. Add 3rd EB Blanco LT 6. Convert EB Blanco T/R to through 7. Add EB Blanco RT 8. Convert SBR & WBR to RTO	RI #15 1. Existing Improvements AND 2. Add 2nd NB Davis RT 3. Add 2nd SB Davis through 4. Add 2nd WB Blanco LT	Same As Background	Same As Background	Same As Background
22	River Terrace Drive*	River Road	NB 1-L/R* EB 1-T, 1-T/R* WB 1-L/T, 1-T*	Stop Sign (NB) WA (NB)	C (Mon. County)	N/A	N/A	Proposed Lane Configurations: NB: 1-L/R EB: 1-T, 1-T/R WB: 1-L, 2-T	None Recommended	None Recommended

Notes:

1. L, T, R = Left, Through, Right
2. NB, SB, EB, WB = Northbound, Southbound, Eastbound, Westbound
3. RTO = Right-turn overlap phasing
4. RI = Recommended Improvement
5. The 2nd NBL and 2nd WBT are included in the Salinas TFO; the 3rd WBL and east and south receiving lanes are not. This would only improve intersection operations to LOS D during the PM peak hour.

* Future intersection and lane configurations

Road Segment		Type	LOS Standard	Existing Conditions	Background Conditions	Background + Project Conditions	Cumulative Conditions
1 Highway 68	Between Josselyn Canyon Rd. and Olmsted Rd.	2-Lane Rural Highway	C/D	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*
2 Highway 68	Between Olmsted Rd. and Highway 218	2-Lane Rural Highway	C/D	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*
3 Highway 68	Between Highway 218 and Ragsdale Dr.	4-Lane Highway	C/D	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*
4 Highway 68	Between Ragsdale Dr. and York Rd.	2-Lane Rural Highway	C/D	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*
5 Highway 68	Between York Rd. and Boots Rd.-Pasadera Dr.	2-Lane Rural Highway	C/D	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*
6 Highway 68	Between Boots Rd.-Pasadera Dr. and Laureles Grade Rd.	2-Lane Rural Highway	C/D	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*
7 Highway 68	Between Laureles Grade Rd. and Corral de Tierra Rd.	2-Lane Rural Highway	C/D	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*
8 Highway 68	Between Corral de Tierra Rd. and San Benancio Rd.	2-Lane Rural Highway	C/D	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*
9 Highway 68	Between San Benancio Rd. and Torero Dr.	2-Lane Rural Highway	C/D	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*
10 Highway 68	Between Torero Dr. and Begin/End Freeway	2-Lane Rural Highway	C/D	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*	Widen Highway 68 to 4 Lanes*
11 Highway 68	Between Begin/End Freeway and Portola Dr.	4-Lane Freeway	C/D	None Recommended	None Recommended	None Recommended	None Recommended
12 Highway 68	Between Portola Dr. and Reservation Rd.	4-Lane Freeway	C/D	None Recommended	None Recommended	None Recommended	None Recommended
13 Highway 68	Between Reservation Rd. and Spreckels Blvd.	4-Lane Freeway	C/D	None Recommended	None Recommended	None Recommended	None Recommended
14 Highway 68	Between Spreckels Blvd. and Blanco Rd.	Multi-Lane Highway	C/D	None Recommended	None Recommended	None Recommended	None Recommended
15 Highway 218	Between Highway 68 and General Jim Moore Blvd.	2-Lane Rural Highway	C/D	Widen Highway 218 to 4 lanes between Highway 68 and General Jim Moore Blvd.	Widen Highway 218 to 4 lanes between Highway 68 and General Jim Moore Blvd.	Widen Highway 218 to 4 lanes between Highway 68 and General Jim Moore Blvd.	Widen Highway 218 to 4 lanes between Highway 68 and General Jim Moore Blvd.
16 Reservation Rd.	Between Highway 68 and Davis Rd.	2-Lane Rural Highway	C	Widen Reservation Rd. to 4 lanes between Highway 68 and Davis Rd.	Widen Reservation Rd. to 4 lanes between Highway 68 and Davis Rd.	Widen Reservation Rd. to 4 lanes between Highway 68 and Davis Rd.	Widen Reservation Rd. to 4 lanes between Highway 68 and Davis Rd.
17 Davis Rd.	Between Reservation Rd. and Blanco Rd.	2-Lane Rural Highway	C	Widen Davis Rd. to 4 lanes between Reservation Rd. and Blanco Rd.	Widen Davis Rd. to 4 lanes between Reservation Rd. and Blanco Rd.	Widen Davis Rd. to 4 lanes between Reservation Rd. and Blanco Rd.	Widen Davis Rd. to 4 lanes between Reservation Rd. and Blanco Rd.

* Or Construct Highway 68 Bypass

Exhibit 7
Recommended Improvements