Intersection						Existing Conditions				Background Conditions				Background + Project Conditions				Background + Alternative Project Site Plan Conditions				Cumulative + Project Conditions			
						AM Peak Hr		PM Peak Hr		AM Peak Hr		PM Peak Hr		AM Peak Hr		PM Peak Hr		AM Peak Hr		PM Peak Hr		AM Peak Hr		PM Peak Hr	
	N-S Street	E-W Street	Existing Lane Configuration	Existing Intersection Control	LOS Standard (Jurisdiction)	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS
1	Josselyn Canyon Road	Highway 68	NB 1-L, 1-R EB 1-T, 1-R WB 1-L, 1-T	Signal	C/D (Caltrans)	34.9	C	35.9	D	43.9	D	66.6	E	**45.4**	**D**	**69.3**	**E**	**44.7**	**D**	**68.4**	**E**	181.6	F	192.3	F
					RI #1	34.7	C	34.5	C																
					RI #12					9.2	A	7.0	A	9.5	A	7.1	A	9.6	A	7.1	A	14.2	B	9.4	A
2	Olmsted Road	Highway 68	NB 1-L/T/R SB 1-L/T, 1-R EB 1-L, 1-T, 1-R WB 1-L, 1-T, 1-R	Signal	C/D (Caltrans)	65.1	E	109.1	F	66.0	E	168.2	F	**68.8**	**E**	**172.6**	**F**	**67.9**	**E**	**171.2**	**F**	222.7	F	*	F
					RI #2	26.7	C	28.0	C	25.8	C	29.9	C	25.8	C	30.5	C	25.7	C	30.4	C				
					RI #16																	20.1	C	31.8	C
3	Highway 218	Highway 68	NB 1-L, 1-T/R SB 2-L, 1-T, 1-R EB 1-L, 1-T, 1-T/R WB 1-L, 2-T, 1-R	Signal	C/D (Caltrans)	21.6	C	24.3	C	22.8	C	32.9	C	23.0	C	33.7	C	23.0	C	33.3	C	63.9	E	111.4	F
					RI #17																	26.6	C	33.5	C
4	Ragsdale Drive	Highway 68	SB 2-R EB 1-L, 2-T WB 1-T, 1-T/R	Half Signal	C/D (Caltrans)	14.1	B	12.7	B	19.5	B	12.7	B	20.0	B	12.7	B	19.9	B	12.7	B	42.7	D	19.4	B
					RI #18																	14.4	B	17.7	B
5	York Road	Highway 68	SB 1-L, 1-R EB 1-L, 1-T WB 1-T, 1-R	Signal	C/D (Caltrans) Including 2nd SBL & 4th Leg	63.6	E	76.3	E	87.5	F	81.7	F	**91.6**	**F**	**86.1**	**F**	**91.1**	**F**	**85.0**	**F**	178.5	F	180.5	F
					RI #3	21.6	C	23.3	C	28.0	C	32.5	C	28.3	C	33.1	C	28.2	C	33.0	C				
					RI #19																	29.9	C	27.4	C
6	Pasadera Drive-Boots Road	Highway 68	NB 1-L, 1-T/R SB 1-L/T, 1-R EB 1-L, 1-T, 1-R WB 1-L, 1-T, 1-R	Signal	C/D (Caltrans)	36.8	D	29.6	C	73.8	E	44.4	D	**78.5**	**E**	**49.5**	**D**	**77.9**	**E**	**48.5**	**D**	189.9	F	184.6	F
					RI #4	10.4	B	19.9	B	12.4	B	25.2	C	12.5	B	28.0	C	12.5	B	27.8	C				
					RI #20																	13.3	B	14.5	B
7	Laureles Grade Road	Highway 68	NB 1-L, 1-R EB 1-T, 1-R WB 1-L, 1-T	Signal	C/D (Caltrans) Including 2nd WBL	38.8	D	82.6	F	60.3	E	91.2	F	**64.7**	**E**	**98.8**	**F**	**63.8**	**E**	**98.0**	**F**	173.0	F	226.5	F
					RI #5	15.4	B	29.6	C	15.3	B	26.7	C	15.7	B	27.6	C	15.6	B	27.6	C				
					RI #21																	18.5	B	26.8	C

Notes:

1. L, T, R = Left, Through, Right
2. NB, SB, EB, WB = Northbound, Southbound, Eastbound, Westbound
3. WA = Worst Approach
4. Levels of service in **BOLD** represent significant project impacts
5. Recommended improvements (RI) are described on Exhibit 7

Intersection						Existing Conditions				Background Conditions				Background + Project Conditions				Background + Alternative Project Site Plan Conditions				Cumulative + Project Conditions			
						AM Peak Hr		PM Peak Hr		AM Peak Hr		PM Peak Hr		AM Peak Hr		PM Peak Hr		AM Peak Hr		PM Peak Hr		AM Peak Hr		PM Peak Hr	
	N-S Street	E-W Street	Existing Lane Configuration	Existing Intersection Control	LOS Standard (Jurisdiction)	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS
8	Corral de Tierra Road	Highway 68	NB 1-L, 1-R EB 1-T, 1-R WB 1-L, 1-T	Signal	C/D (Caltrans) Including 2nd WBL & 4th Leg	35.6	D	68.1	E	127.6	F	143.7	F	**135.4**	**F**	**154.9**	**F**	**134.0**	**F**	**153.3**	**F**	*	F	*	F
					RI #6	19.0	B	22.1	C	27.8	C	21.6	C	26.3	C	21.7	C	24.3	C	21.7	C				
					RI #22																	34.6	C	32.3	C
9	San Benancio Road	Highway 68	NB 1-L/T, 1-R SB 1-L/T, 1-R EB 1-L, 1-T, 1-R WB 1-L, 1-T/R	Signal	C/D (Caltrans) Including 2nd WBL	71.5	E	113.2	F	82.5	F	135.2	F	**90.4**	**F**	**147.0**	**F**	**88.1**	**F**	**144.3**	**F**	264.1	F	*	F
					RI #7	22.1	C	17.5	B	19.6	B	23.6	C	21.0	C	24.4	C	18.5	B	23.7	C	26.7	C	19.5	B
10	Paseo de Vaqueros	San Benancio Road	NB 1-L/T SB 1-T/R EB 1-L/R	Stop Sign (EB) WA (EB)	C (Mon. County)	1.2 11.5	A B	0.7 11.4	A B	1.1 11.9	A B	0.7 12.0	A B	1.3 12.9	A B	0.9 13.2	A B	1.2 12.7	A B	0.7 12.8	A B	1.3 13.9	A B	0.9 13.8	A B
11	Torero Drive	Highway 68	SB 1-L, 1-R EB 1-L, 1-T WB 1-T, 1-R	Stop Sign (SB) WA (SB)	C/D (Caltrans)	68.9 *	F F	1.0 37.0	A E	91.2 *	F F	1.1 53.9	A F	**96.3** *****	**F** **F**	1.2 **59.1**	A **F**	**95.9** *****	**F** **F**	1.2 **57.5**	A **F**	* *	F F	6.4 *	A F
					RI #8	18.3	B	20.1	C																
					RI #13					22.4	C	10.2	B	22.5	C	10.0	A	22.8	C	13.7	B	26.3	C	7.7	A
12	Portola Drive	Highway 68 EB Ramps	NB 1-L, 1-T/R SB 1-L, 1-T/R EB 1-L/T/R WB 1-L/T/R	All-Way Stop	C/D (Caltrans)	7.6	A	7.3	A	7.6	A	7.3	A	8.8	A	8.3	A	8.6	A	8.3	A	11.1	B	9.5	A
13	Portola Drive	Highway 68 WB Ramps	NB 1-L, 1-T/R SB 1-L, 1-T/R EB 1-L/T/R WB 1-L/T/R	All-Way Stop	C/D (Caltrans) *RI #23*	17.1	C	9.4	A	17.1	C	9.4	A	20.3	C	10.7	B	20.0	C	10.6	B	82.4 16.1	F B	17.6 10.0	C A
14	Highway 68 EB Ramps	River Road	NB 1-L/T, 1-R EB 1-L, 1-T WB 1-T, 1-R	Signal	C/D (Caltrans) *RI #24*	17.7	B	11.6	B	19.7	B	12.6	B	21.0	C	13.1	B	20.8	C	12.9	B	129.7 34.6	F C	20.6 14.2	C B

Notes:

1. L, T, R = Left, Through, Right
2. NB, SB, EB, WB = Northbound, Southbound, Eastbound, Westbound
3. WA = Worst Approach
4. Levels of service in **BOLD** represent significant project impacts
5. Recommended improvements (RI) are described on Exhibit 7

Intersection						Existing Conditions				Background Conditions				Background + Project Conditions				Background + Alternative Project Site Plan Conditions				Cumulative + Project Conditions			
						AM Peak Hr		PM Peak Hr		AM Peak Hr		PM Peak Hr		AM Peak Hr		PM Peak Hr		AM Peak Hr		PM Peak Hr		AM Peak Hr		PM Peak Hr	
	N-S Street	E-W Street	Existing Lane Configuration	Existing Intersection Control	LOS Standard (Jurisdiction)	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	Delay (sec)	LOS
15	Highway 68 WB Ramps	Reservation Road	SB 1-L/T, 1-R EB 1-T/R WB 1-L, 1-T	Signal	C/D (Caltrans) *RI #25*	21.9	C	22.4	C	25.2	C	27.7	C	27.6	C	29.9	C	26.4	C	28.7	C	116.0 23.1	F C	173.5 29.7	F C
16	Highway 68 WB Ramps	Spreckels Boulevard	SB 1-L/T/R EB 1-T/R WB 1-L/T	Stop Sign (SB) WA (SB)	C/D (Caltrans) *RI #26*	11.5 20.7	B C	11.5 22.1	B C	12.4 28.5	B D	14.9 46.6	B E	12.4 29.0	B D	15.1 48.0	C E	12.4 28.8	B D	15.1 48.0	C E	* * 10.2	F F B	* * 13.1	F F B
17	Highway 68 EB Offramp	Spreckels Boulevard	NB 1-L, 1-R EB 1-T WB 1-T	Stop Sign (NB) WA (NB)	C/D (Caltrans) *RI #27*	4.7 10.9	A B	2.8 9.8	A A	4.7 11.1	A B	3.6 10.6	A B	4.7 11.1	A B	3.7 10.7	A B	4.7 11.1	A B	3.7 10.6	A B	116.2 240.5 22.4	F F C	66.0 157.6 11.6	F F B
18	Highway 68 EB Onramp	Spreckels Boulevard	SB 1-L, 1-R EB 1-L, 1-T WB 1-T, 1-R	Stop Sign (SB) WA (EB)	C/D (Caltrans) *RI #28*	0.1 0.1	A A	0.7 26.5	A D	0.1 0.1	A A	0.3 30.4	A D	0.1 0.1	A A	0.3 30.5	A D	0.1 0.1	A A	0.3 30.5	A D	0.8 190.9 0.3 70.3	A F A F	0.4 127.8 0.2 60.2	A F A F
19	Highway 68	Blanco Road	NB 1-L, 2-T, 1-R SB 1-L, 2-T, 1-R EB 2-L, 2-T, 1-R WB 2-L, 1-T, 1-T/R	Signal	C/D (Caltrans) *RI #9*	38.6 28.8	D C	45.5 31.8	D C	44.9 31.4	D C	59.6 39.4	E D	**45.6** 33.4	**D** C	**62.9** 42.3	**E** D	**45.4** 33.7	**D** C	**62.2** 42.1	**E** D	57.1 33.9	E C	84.1 51.1	F D
20	Davis Road	Reservation Road	NB 1-L/T/R SB 1-L/T, 1-R EB 1-L, 1-T/R WB 1-L, 1-T/R	Stop Sign (NB & SB) WA (SB)	C (Mon. County) *RI #10* *RI #14*	16.7 52.8 21.0	C F C	44.1 195.0 24.3	E F C	* * 21.1	F F C	* * 34.3	F F C	***** ***** 21.7	**F** **F** C	***** ***** 33.7	**F** **F** C	***** ***** 21.6	**F** **F** C	***** ***** 33.6	**F** **F** C	* * 18.2	F F B	* * 33.8	F F C
21	Davis Road	Blanco Road	NB 1-L, 1-T, 1-T/R SB 1-L, 1-T, 1-R EB 2-L, 1-T, 1-T/R WB 1-L, 2-T, 1-R	Signal	C (Mon. County) *RI #11* *RI #15*	31.9 23.5	C C	38.3 32.0	D C	39.6 24.4	D C	86.2 30.6	F C	**40.1** 24.5	**D** C	**87.6** 31.1	**F** C	**40.0** 24.4	**D** C	**87.4** 31.0	**F** C	114.0 27.5	F C	250.7 32.6	F C
22	River Terrace Drive*	River Road	NB 1-L/R* EB 1-T, 1-T/R* WB 1-L/T, 1-T*	Stop Sign (NB) WA (NB)	C (Mon. County)	N/A				N/A				0.2 18.3	A C	1.4 29.9	A D	0.2 17.9	A C	0.5 24.4	A C	0.2 22.2	A C	1.8 45.1	A E

Notes:

1. L, T, R = Left, Through, Right
2. NB, SB, EB, WB = Northbound, Southbound, Eastbound, Westbound
3. WA = Worst Approach
4. Levels of service in **BOLD** represent significant project impacts
5. Recommended improvements (RI) are described on Exhibit 7

* Future intersection and lane configurations